### (19) World Intellectual Property Organization International Bureau



### (43) International Publication Date 20 February 2003 (20.02.2003)

#### PCT

### (10) International Publication Number WO 03/013620 A1

(51) International Patent Classification7: H01T 23/00 A61L 9/22,

(21) International Application Number: PCT/JP02/08106

(22) International Filing Date: 7 August 2002 (07.08.2002)

(25) Filing Language:

English

(26) Publication Language:

English

(30) Priority Data: 2001-239908


7 August 2001 (07.08.2001) JP


(71) Applicant (for all designated States except US): SHARP KABUSHIKI KAISHA [JP/JP]; 22-22, Nagaike-cho, Abeno-ku, Osaka-shi, Osaka 545-8522 (JP). (72) Inventors; and

- (75) Inventors/Applicants (for US only): SEKOGUCHI, Yoshinori [JP/JP]; c/o SHARP KABUSHIKI KAISHA, 22-22, Nagaike-cho, Abeno-ku, Osaka-shi, Osaka 545-8522 (JP). YAMAMOTO, Masahito [JP/JP]; c/o SHARP KABUSHIKI KAISHA, 22-22, Nagaike-cho, Abeno-ku, Osaka-shi, Osaka 545-8522 (JP). MORIKAWA, Mamoru [JP/JP]; c/o SHARP KABUSHIKI KAISHA, 22-22, Nagaike-cho, Abeno-ku, Osaka-shi, Osaka 545-8522 (JP).
- (74) Agent: KOHNO, Takao; C/O KOHNO PATENT OF-FICE, 4-3, Tsuriganecho 2-chome, Chuo-ku, Osaka-shi, Osaka 540-0035 (JP).
- (81) Designated States (national): AE, AG, AL, AM, AT, AU, AZ, BA, BB, BG, BR, BY, BZ, CA, CH, CN, CO, CR, CU, CZ, DE, DK, DM, DZ, EC, EE, ES, FI, GB, GD, GE, GH, GM, HR, HU, ID, IL, IN, IS, KE, KG, KP, KR, KZ, LC,

[Continued on next page]

(54) Title: ION GENERATING ELEMENT AND ION GENERATOR, AIR CONDITIONING APPAR ATUS, CLEANER AND REFRIGERATOR CONTAINING THE SAME





(57) Abstract: ABSTRACT The present invention includes an inner electrode 6 formed inside a dielectric body 4 and a surface electrode 5 formed on a surface of the dielectric body 4, and the surface electrode 5 is formed in a grid pattern with acuminate parts 5a formed inside the grid squares. More specifically, each acuminate part 5a is made of a triangle whose vertices are two arbitrary points on a side of the grid square and an arbitrary point inside the grid square, or a quadrangle whose vertices are a crossing of grid lines, an arbitrary point near a straight line connecting crossings of grid lines in the diagonal positions, and two arbitrary points on sides of the grid square. The present invention provides an ion generating element capable of generating positive ions and negative ions in a stable manner even under a wide range of applied voltage while curbing the increase in noise, and capable of decreasing the generation of ozone, and provides an ion generator, air conditioning apparatus, cleaner and refrigerator using this ion generating element.

NO 03/013620 A1

LK, LR, LS, LT, LU, LV, MA, MD, MG, MK, MN, MW, MX, MZ, NO, NZ, OM, PH, PL, PT, RO, RU, SD, SE, SG, SI, SK, SL, TJ, TM, TN, TR, TT, TZ, UA, UG, US, UZ, VN, YU, ZA, ZM, ZW.

(84) Designated States (regional): ARIPO patent (GH, GM, KE, LS, MW, MZ, SD, SL, SZ, TZ, UG, ZM, ZW), Eurasian patent (AM, AZ, BY, KG, KZ, MD, RU, TI, TM), European patent (AT, BE, BG, CH, CY, CZ, DE, DK, EE, ES, FI, FR, GB, GR, IE, IT, LU, MC, NL, PT, SE, SK,

TR), OAPI patent (BF, BJ, CF, CG, CI, CM, GA, GN, GQ, GW, ML, MR, NE, SN, TD, TG).

#### Published:

- with international search report

For two-letter codes and other abbreviations, refer to the "Guidance Notes on Codes and Abbreviations" appearing at the beginning of each regular issue of the PCT Gazette.

WO 03/013620 PCT/JP02/08106

1

#### DESCRIPTION

ION GENERATING ELEMENT AND ION GENERATOR, AIR CONDITIONING APPARATUS, CLEANER AND REFRIGERATOR CONTAINING THE SAME

5

10

20

25

30

#### TECHNICAL FIELD

The present invention relates to an ion generating element capable of emitting both of positive ions and negative ions into a space and disinfecting bacteria floating in the air, an ion generator using the ion generating element, an air conditioning apparatus, cleaner and refrigerator using the ion generator. The present invention more particularly relates to an ion generating element capable of emitting positive ions and negative ions in a stable manner, reducing noise caused by the emission of ions, and decreasing the emission of ozone by designing a surface electrode formed on a surface of a dielectric body to have a special shape.

In general, in a closed room which is ventilated less frequently, such as an office and a conference room, when there are many people in the room, the air polluting substances such as carbon dioxide discharged by breathing, smoke of cigarettes and dust increase, and consequently negative ions which have the effect of relaxing human are reduced in the air. Sometimes a large amount of negative ions are lost by cigarette smoke particularly and the negative ions are reduced to about 1/2 to 1/5 of the usual amount.

Therefore, a number of ion generators have been sold in the market to supply negative ions into the air, but all the generators just generate only negative ions by a DC high voltage system. Such a conventional ion generator for generating only negative ions can supply negative ions into the air, but can not positively remove the floating bacteria in the air.

The present inventors eagerly studied and, as a result, have invented a structure of emitting  $H^+(H_2O)_n$  (n is a natural number) as positive ions and

WO 03/013620 PCT/JP02/08106

2

O<sub>2</sub>-(H<sub>2</sub>O)<sub>m</sub> (m is a natural number) to enclose the floating bacteria in the air with the ions, make a chemical reaction, and disinfect the floating bacteria in the air by the decomposition function of hydrogen peroxide (H<sub>2</sub>O<sub>2</sub>) and/or hydroxyl radical (OH) that are active species generated in the chemical reaction.

5

10

15

20

25

30

The applicant of the present application proposed in Japanese Patent Application No. 2001-166118 an ion generating element comprising a surface electrode formed on a surface of a dielectric body, and an inner electrode provided in parallel to the surface electrode inside the dielectric body. FIG. 10 is a perspective view showing the ion generating element, and FIG. 11 is a cross sectional view of the ion generating element. As shown in these figures, a dielectric body 104 made of ceramics is composed of an upper dielectric body 102 and a lower dielectric body 103, and a strip-like inner electrode 106 is formed between the upper dielectric body 102 and the lower dielectric body 103.

On the other hand, on a surface of the upper dielectric body 102, a surface electrode 105 is formed in parallel to the inner electrode 106. The surface electrode 105 is screen printed using tungsten, on the upper dielectric body 102, and also formed in a grid pattern as shown in FIG. 10 so as to emit a large amount of positive ions and negative ions into the air. In short, the grid-like surface electrode 105 is formed on a surface of the dielectric body 102 by screen printing so as to efficiently generate positive ion and negative ions.

In addition, the ion generating element 101 comprises: a coating layer 109, made of alumina or the like, covering the surfaces of the dielectric body 102 and surface electrode 105; a surface electrode connecting part 111 whose one end is connected to the surface electrode 105 and the other end is connected to a surface electrode contact 108 provided on the lower face of the lower dielectric body 103; and an inner electrode conducting part 112 whose one end is connected to the inner electrode 106 and the other end is

15

20

25

30

connected to an inner electrode contact 107 provided on the lower face of the lower dielectric body 103. By connecting the inner electrode contact 107 and the surface electrode contact 108 to a voltage applying circuit, not shown, and applying an AC voltage to the inner electrode 106 and the surface electrode 105 formed in a grid pattern on a surface of the upper dielectric body 102, a large amount of positive ions and negative ions are generated.

In the ion generating element proposed in Japanese Patent Application No. 2001-166118, however, it is necessary to take a voltage fluctuation during the actual use into account and apply a voltage for satisfactory generation of ions. In other words, the relation between the voltage and ion generation has characteristics that ions are generated by application of a voltage equal to or higher than a certain value and the amount of ions increases with an increase in the voltage, but the ion increase rate decreases when a higher voltage is applied. In a stable region, there is a problem of big discharge sound on the electrode surface, and it is necessary to decrease noise as small as possible in actual application.

Furthermore, since ozone harmful to human body is generated with the generation of ions, it is necessary to decrease the generation of ozone as low as possible while maintaining the emission of ions.

The inventors of the present application conducted experiments repeatedly by changing the conditions of the surface electrode formed on a surface of the dielectric body, and found that it was possible to generate ions from a lower voltage region and generate ions in a stable manner in a wide range of applied voltage by further extending the grid-like surface electrode to form a pointed surface electrode inside the grid squares. Accordingly, since stable ion generation is performed even at a low voltage, the inventors also found that it was possible to reduce noise and the generation of ozone by optimizing the shape and size of the surface electrode.

The present invention has been made based on the findings and with the aim of solving the above problems, and it is an object of the present

15

20

25

30

invention to provide an ion generator capable of generating positive ions and negative ions in a stable manner under a wide range of applied voltage while reducing noise and also capable of reducing the generation of ozone, by forming the surface electrode in a special shape, and to provide an ion generator using the ion generating element.

Moreover, it is another object of the present invention to provide an air conditioning apparatus capable of being incorporated in various apparatuses such as an air conditioner, a microwave oven and a washing/drying machine by using the ion generator of the present invention and a blower for sending ions generated by the ion generator to the outside.

Furthermore, it is still another object of the present invention to provide a cleaner and a refrigerator, capable of effectively reducing dirt in air such as dust generated during cleaning and unpleasant smells in the refrigerator, by installing the ion generator of the present invention and a blower for sending the generated ions out of the cleaner or into the refrigerator.

#### DISCLOSURE OF THE INVENTION

An ion generating element according to the present invention comprises: a dielectric body; an inner electrode formed inside the dielectric body; and a surface electrode formed on a surface of the dielectric body, and is characterized in that the surface electrode is formed in a grid pattern and has a pointed part in each grid square.

The ion generating element according to the present invention is characterized in that the pointed part is made of a triangle whose vertices are two arbitrary points on a side of the grid square and an arbitrary point inside the grid square.

The ion generating element according to the present invention is characterized in that a plurality of the triangles are formed for each grid square, and the distance between the vertices of the triangles inside the grid

**15** 

20

25

30

square is not less than 0.25 mm but not more than 0.5 mm.

The ion generating element according to the present invention is characterized in that the pointed part is made of a quadrangle whose vertices are a crossing of grid lines, an arbitrary point near a straight line connecting crossings of grid lines in diagonal positions, and two arbitrary points on sides of the grid square.

The ion generating element according to the present invention is characterized in that the pitch of the grid is not less than 1.0 mm but not more than 1.5 mm.

The ion generating element according to the present invention comprises: a plate-like dielectric body; an inner electrode formed inside the dielectric body; and a surface electrode formed on a surface of the dielectric body, and is characterized in that the inner electrode lies inside the extent of the surface electrode.

An ion generator according to the present invention comprises: an ion generating element of the present invention; and a voltage applying circuit for applying a voltage to the surface electrode and the inner electrode of the ion generating element, and is characterized by generating  $H^{\dagger}(H_2O)_n$  (n is a natural number) and  $O_2^{-}(H_2O)_m$  (m is a natural number) in the air by application of a voltage by the voltage applying circuit.

An air conditioning apparatus according to the present invention is characterized by including an ion generator of the present invention, and a blower for sending ions generated by the ion generator to the outside.

A cleaner according to the present invention is characterized by including an ion generator of the present invention, and a blower for emitting ions generated by the ion generator out of the cleaner.

A refrigerator according to the present invention is characterized by including an ion generator of the present invention, and a blower for emitting ions generated by the ion generator into the refrigerator.

According to the present invention, on a surface of the dielectric body,

in addition to the grid-like surface electrode, the pointed surface electrode is formed inside the grid squares. More specifically, a triangle having two arbitrary points on a side of a grid square and an arbitrary point inside the grid square as the vertices, or a quadrangle having a crossing of grid lines, an arbitrary point near a straight line connecting crossings of grid lines in the diagonal positions, and two arbitrary points on sides of the grid square as the vertices is formed as an extended part. Thus, by further providing the surface electrode with the pointed parts, it is possible to generate positive ions and negative ions in a stable manner in a wide range of voltage application. Accordingly, ion generation at a low voltage becomes possible. and noise and the generation of ozone can be effectively reduced by decreasing the voltage. Since the present invention can generate ions in a stable manner without particularly depending on the strength of the applied voltage, the ion generating element of the present invention can be incorporated in numerous apparatuses regardless of the types of apparatuses and conditions of use such as home use or business use.

#### BRIEF DESCRIPTION OF THE DRAWINGS

10

15

20

25

30

FIG. 1 is a schematic perspective view showing the structure of an ion generating element according to the present invention and the configuration of a surface electrode by enlargement; FIG. 2 is a plan view of the ion generating element; FIG. 3 is a cross sectional view cut along the III-III line of FIG. 1; FIG. 4 is a cross sectional view cut along the IV-IV line of FIG. 1; FIG. 5 is an enlarged view showing the detail of the surface electrode; FIG. 6 is an explanatory view showing another embodiment of the surface electrode; FIG. 7 is an explanatory view showing still another embodiment of the surface electrode; FIG. 8 is a schematic diagram showing the essential section of a cleaner using an air conditioning apparatus; FIG. 9 is a schematic diagram showing the essential section in a refrigerator using an air conditioning apparatus; FIG. 10 is a perspective view showing a

10

15

20

25

30

conventional ion generating element; and FIG. 11 is a cross sectional view of the conventional ion generating element.

#### BEST MODE FOR CARRYING OUT THE INVENTION

The following description will explain the present invention in detail with reference to the drawings illustrating some embodiments thereof.

FIG. 1 is a schematic perspective view showing the structure of an ion generating element according to the present invention and the configuration of a surface electrode by enlargement; FIG. 2 is a plan view of the ion generating element; FIG. 3 is a cross sectional view cut along the III-III line of FIG. 1; and FIG. 4 is a cross sectional view cut along the IV-IV line of FIG. 1.

An ion generating element 1 of the present invention comprises: a surface electrode 5 formed on a surface of a plate-like dielectric body 4, in a grid pattern with pointed parts 5a formed in the grid squares (a structure including the grid part and the pointed parts 5a will be hereinafter referred to as the surface electrode 5); a surface electrode contact 8, provided on the lower face of the dielectric body 4, for supplying electric power to the surface electrode 5; a strip-like inner electrode 6 buried inside the dielectric body 4 so as to be substantially parallel to the surface electrode 5; and an inner electrode contact 7, provided on the lower face of the dielectric body 4 for supplying electric power to the inner electrode 6. Note that the dielectric body 4 is composed of an upper dielectric body 2 and a lower dielectric body 3.

The following description will explain each structure in detail. An organic material having an excellent oxidation resistance is suitable for the material of the dielectric body 4, and, for example, it is possible to use a resin such as polyimide and glass epoxy. In the case where an inorganic material is to be used, it is possible to use ceramics such as high purity alumina, crystallized glass, forsterite and steatite. When the corrosion

PCT/JP02/08106 WO 03/013620

8

resistance is taken into consideration, inorganic materials are preferred. When the moldability and the later-described easiness in constructing the electrode are taken into consideration, it is suitable to use ceramics for Since it is desirable to have a uniform insulating resistance between the surface electrode 5 and the inner electrode 6, material with a low internal density and the dielectric body 4 with a uniform insulation rate are more preferred.

The dielectric body 4 can have a circular, oval or other shape including a polygon shape, or even have a cylindrical shape. However, 10 when the productivity is taken into consideration, it is preferred that the dielectric body 4 is in the form of a plate as shown in the drawing. Although the material for the surface electrode 5 is not particularly limited as long as it has conductivity, but the material needs to satisfy a condition that it does not cause deformation such as melting by discharge. In this embodiment, the surface electrode 5 is formed by screen-printing tungsten on a surface of the dielectric body 4. Note that, when the surface electrode 5 is formed so as to protrude from the surface of the dielectric body 4, it is preferred that the protruding section has a uniform thickness. On the other hand, when the surface electrode 5 is formed on the inner electrode 6 side than the surface of the dielectric body 4, it is preferred that the depth thereof is uniform.

15

20

25

30

As shown in FIG. 1, the surface electrode 5 is formed in a grid pattern and further has pointed parts extended in the inward direction of the grid squares. FIG. 5 is an enlarged view showing the detail of the surface electrode 5. As shown in FIG. 5, the pitch (w) of the grid of the surface electrode 5 is not less than 1.0 mm but not more than 1.5 mm, and preferably 1.2 mm. The extended pointed part is in the shape of a triangle drawn by connecting two arbitrary points (point A and point B) on a side of the grid square and an arbitrary point C inside the grid square. A distance g between the point A and the point B is about 0.25 mm to 0.45 mm, and a WO 03/013620 PCT/JP02/08106

9

height h of the triangle (the length of a perpendicular dropped from the point C to a straight line connecting the point A and the point B) is preferably 0.25 mm to 0.35 mm. Similarly, a distance f between the vertices (between a point C and a point C) of the triangles inside the grid square is not less than 0.25 mm but not more than 0.5 mm, and more preferably 0.35 mm. Note that the propriety of the above mentioned values is examined by the later-described experiments.

Moreover, although this embodiment is explained on the assumption that the point A and the point B of the triangle are located in the approximately center section of a side of the grid square and the triangle is an equilateral triangle or an isosceles triangle with the point C as the vertex, the triangle is not necessarily limited to such a shape, the positions of the point A and point B can be located in any position on a side of the grid square as long as the extended part has a pointed shape, and the triangle can be a scalene triangle.

10

15

20

25

30

FIG. 6 is an explanatory view showing another embodiment of the surface electrode 5. As another pointed shape, it is possible to use a quadrangle whose vertices are a crossing D of grid lines, an arbitrary point C near a straight line connecting the crossings D and D in the diagonal positions, and two arbitrary points (point A and point B) on sides of the grid square. Like the above-mentioned triangular shape, the distance f between the vertices (between a point C and a point C) inside the grid square is not less than 0.25 mm but not more than 0.5 mm, and more preferably 0.35 mm. A distance j between the point A and the point D and a distance j between the point B and the point D are both preferably about 0.15 mm, and a distance k between the point C to a side the grid square crosses the side is preferably about 0.3 mm.

FIG. 7 is an explanatory view showing still another embodiment of the surface electrode 5. As shown in FIG. 7, it is not necessarily to provide WO 03/013620 PCT/JP02/08106

the pointed triangle on all the sides of the grid squares, and the pointed triangles may be provided on only one side as shown in FIG. 7(a), on two sides to face each other as shown in FIG. 7(b), or on two adjacent sides of each grid square as shown in FIG. 7(c). Although not shown, needless to say, the extended triangles may be formed on three sides of each grid square, except for one side. Similarly, the number of quadrangles can be 1, 2, 3 or 4, and as shown in FIG. 7(d), pointed quadrangles may be formed in two diagonal positions.

Next, referring to FIG. 1 through FIG. 4, the following description will explain the inner electrode 6. For the inner electrode 6, it is possible to use a material having conductivity such as tungsten, for example, and the inner electrode 6 is formed in a strip form on a surface of the upper dielectric body 2 or the lower dielectric body 3. As shown in FIG. 3, the inner electrode 6 is formed between the upper dielectric body 2 and the lower dielectric body 3. In particular, when the insulation resistance between the surface electrode 5 and the inner electrode 6 is uniform, since the discharge state is stable and positive ions and negative ions can be generated in a stable manner, it is desirable that the surface electrode 5 and the inner electrode 6 be parallel to each other. In other words, the inner electrode 6 is positioned inside the dielectric body 4 so that the inner electrode 6 faces and is parallel to the surface electrode 5 and that the distance between the surface electrode 5 and the inner electrode 6 (the interelectrode distance) is uniform.

The surface electrode contact 8 shown in FIG. 3 is a contact connected to the surface electrode 5, and the surface electrode 5 and other construction are connected by connecting one end of a lead wire made of copper, aluminum or the like to this contact and connecting the other end to a contact of the other construction. Since the surface electrode contact 8 and the lead wire are easily connected, the surface electrode contact 8 can be provided at any position as long as it is on a surface of the dielectric body 4.

10

15

20

25

30

However, the surface electrode contact 8 will have the same electric potential as the surface electrode 5, it is desirable that the distance between the inner electrode 6 and the surface electrode contact 8 be longer than the interelectrode distance. By satisfying this desirable relationship, a stable discharge state can be obtained.

The inner electrode contact 7 is a contact connected to the inner electrode 6, and the inner electrode 6 and other construction are connected by connecting one end of a lead wire made of copper, aluminum or the like to this contact and connecting the other end to a contact of the other construction. Since the inner electrode contact 7 and the lead wire are easily connected, the inner electrode contact 7 can be provided at any position as long as it is on a surface of the dielectric body 4. However, since the inner electrode contact 7 will have the same electric potential as the inner electrode 6, it is desirable that the distance between the surface electrode 5 and the inner electrode contact 7 be longer than the interelectrode distance. By satisfying this desirable relationship, a stable discharge state can be obtained.

Moreover, the distance between the surface electrode contact 8 and the inner electrode contact 7 are made longer than the interelectrode distance. Further, when the surface electrode contact 8 and the inner electrode contact 7 are both provided on a surface (lower face) facing a surface (upper face) where the surface electrode 5 are formed, wires such as lead wires are not laid on the upper face where positive ions and negative ions are generated. Therefore, if a blower is additionally provided to send air to the surface where the surface electrode 5 is formed, the flow of air will never be disturbed by the lead wires, and thus this arrangement is preferable. Similarly, such an effect can also be obtained by providing the surface electrode contact 8 and the inner electrode contact 7 at positions other than on the upper face.

Note that the above mentioned "other construction" means voltage

10

15

20

25

30

applying means or the ground, and there is a case where a voltage is applied by connecting the surface electrode 5 and the inner electrode 6 to a voltage applying circuit V (see FIG. 3).

In this case, when the surface electrode 5 is connected to the ground to have a ground potential and the internal electrode 6 is connected to the voltage applying circuit V, a high voltage is not applied to the exposed surface electrode 5, and thereby preventing electric shock accidents. FIG. 3 shows an example of such a construction, in which an ion generator 20 is composed of the ion generating element 1 and the voltage applying circuit V.

In order to generate both positive ions and negative ions with a single ion generating element 1, the voltage applied between the surface electrode 5 and the inner electrode 6 by the voltage applying circuit V needs to be an alternating voltage. This alternating voltage is not limited to a sinusoidal alternating voltage that is generally used for commercial power supply (hereinafter the sinusoidal alternating voltage will be referred to as the "AC voltage"), and a rectangular alternating voltage may be applied, or the alternating voltage may be applied using another waveform.

The ion generator 20 according to the present invention can function as an air conditioning apparatus 30 by further incorporating a blower therein. This air conditioning apparatus 30 is used in a space, for example, in a home, a ward and operation room of a hospital, a vehicle, an air plane, a warehouse, a refrigerator, and a machine, and is applied, for example, to an air conditioner, a dehumidifier, a humidifier, an air purifier, a refrigerator, a fan heater, a microwave oven, a washing/drying machine, a cleaner, and a disinfecting apparatus.

FIG. 8 is a schematic diagram showing the essential section of a cleaner 40 using the air conditioning apparatus 30. As shown in FIG. 8, the discharge air which is generated by the suction of air with the cleaner 40 is discharged from external discharge openings 41 of the cleaner 40 via a filter 31 for removing particulates, by a blower 35 composed of a motor 33

15

20

25

connected to a motor driving circuit 34 and a fan 32 connected to the rotation axis of the motor 33.

The air conditioning apparatus 30 according to the present invention comprises the blower 35 and the ion generator 20 disposed close to each other. The motor driving circuit 34 and the voltage applying circuit V are supplied with a voltage in a synchronized manner by a controller, not shown, and the ion generator 20 generates a large amount of  $H^+(H_2O)_n$  and  $O_2^-(H_2O)_m$  inside the cleaner 40. Meanwhile, the blower 35 spreads the positive ions and negative ions generated inside the cleaner 40 into the room space being cleaned, through the external discharge openings 41 by the air blown from the fan 32. With this structure, it is possible to effectively remove dirt in the air generated by the cleaner 40 and dirt in the air caused by the cleaning action.

FIG. 9 is a schematic diagram showing the essential section inside a refrigerator 50 using the air conditioning apparatus 30. Like the cleaner 40 illustrated in FIG. 8, the residual contaminated air is discharged from internal openings 51 of the refrigerator 50 by the blower 35 composed of the motor 33 connected to the motor driving circuit 34 and the fan 32 connected to the rotation axis of the motor 33.

A voltage is applied to the motor driving circuit 34 and the voltage applying circuit V by a controller, not shown, with a timing programmed in advance in a ROM, not shown, in the controller. Then, the ion generator 20 generates a large amount of H<sup>+</sup>(H<sub>2</sub>O)<sub>n</sub> and O<sub>2</sub><sup>-</sup>(H<sub>2</sub>O)<sub>m</sub>. Meanwhile, the blower 35 spreads the generated positive ions and negative ions into the space inside the refrigerator 50 through the internal openings 51 by the air blown from the fan 32. With this structure, it is possible to effectively remove the unpleasant smells generated by the matters cooled in the refrigerator.

Now, referring to FIG. 1 through FIG. 4, the following description will explain a more specific embodiment. The dielectric body 4 of the ion

generating element 1 according this embodiment has a rectangular parallelepiped shape with a width of 15 mm, a length of 37 mm and a thickness of 0.9 mm, and is provided with the strip-like internal electrode 6 which has a size of about 6 mm  $\times$  24 mm and is formed in parallel to the upper face of the dielectric body 4, and the surface electrode 5 which has a width of about 10.8 mm and a length of 27.6 mm and is arranged so that the center line (the III-III line in FIG. 1) connecting the centers of both end lines (about 15 mm-wide side) on the upper face of the dielectric body 4 is the line The surface electrode 5 is formed so that if the surface of symmetry. electrode 5 is projected onto the internal electrode 6, the projection of the surface electrode 5 spreads to an area outside the internal electrode 6, and, if the surface electrode 5 is virtually present on a plane where the internal electrode 6 is formed (in the plan view), a portion corresponding to the periphery of the surface electrode 5 is located outside a portion corresponding to the periphery of the inner electrode 6. By forming the surface electrode 5 in such a manner, when discharge is performed from the inner electrode 6 to the surface electrode 5, the discharge is carried out inside the surface electrode 5, and therefore the discharge state in the air is stable and ions can be generated in a good balance. Note that the shapes and sizes of the grid and pointed triangle, quadrangle, etc. of the surface electrode 5 are the same as those mentioned above.

15

20

25

30

Moreover, the surface electrode contact 8 is provided on the lower face of the dielectric body 4. The surface electrode contact 8 is connected to the surface electrode 5 by an upper-face connecting part 10 having one end connected to the surface electrode 5 and the other end at a position on the upper face of the dielectric body 4 facing the surface electrode contact 8 and a length longer than the interelectrode distance and by a surface electrode connecting part 11 for connecting the other end of the upper-face connecting part 10 to the surface electrode contact 8.

Further, the inner electrode contact 7 is provided at an arbitrary

WO 03/013620 PCT/JP02/08106

5

10

15

20

25

30

15

position on the lower face of the dielectric body 4, facing the inner electrode 6. The inner electrode contact 7 is connected to the inner electrode 6 by an inner electrode connecting part 12. Note that the distance between the surface electrode contact 8 and the inner electrode contact 7 is made longer than the interelectrode distance.

Next, a method for manufacturing the ion generating element 1 is explained. First, a 0.45 mm thick high purity alumina sheet is cut into a predetermined size (15 mm width  $\times$  37 mm length) so as to form two alumina bases having substantially the same size. Note that, alumina with a purity equal to or higher than 90% can be used, and alumina with a purity of 92% is used here.

The surface electrode 5 and the upper face connecting part 10 are integrally formed by screen printing tungsten in a grid pattern on the upper face of one of the two alumina bases so as to fabricate the upper dielectric body 2. Then, tungsten is screen printed in a strip pattern on the upper face of the other alumina base to form the inner electrode 6 integrally on the surface of the alumina base, and the surface electrode contact 8 and the inner electrode contact 7 are formed on the lower face of the alumina base by screen printing, thereby fabricating the lower dielectric body 3.

Further, an alumina coating layer 9 (only shown in FIG. 3) is formed on a surface of the upper dielectric body 2 so as to provide the surface electrode 5 with an insulation coat. After placing the lower face of the upper dielectric body 2 and the upper face of the lower dielectric body 3 one upon another, pressure bonding and vacuum suction are performed, and then they are placed in a furnace and baked under a non oxidation atmosphere at 1400°C to 1600°C. According to this manufacturing process, it is possible to easily manufacture the ion generating element 1 shown in the present invention.

Next, the following description will explain an example in which a voltage was applied to the ion generating element 1 formed by the

WO 03/013620 PCT/JP02/08106

16

above mentioned method. In order to apply a voltage between the surface electrode 5 and the internal electrode 6 of the ion generating element 1, the ion generator 20 is constructed by connecting the voltage applying circuit V and the surface electrode contact 8 with a lead wire, and connecting the inner electrode contact 7 and the voltage applying circuit V with a lead wire. Then, by operating the voltage applying circuit V to apply an AC high voltage between the surface electrode 5 and the inner electrode 6, positive ions and negative ions are generated.

10

15

20

25

30

The following description will explain experiments which were performed by changing the shape of the surface electrode 5 so as to examine the influence of the change in the shape on the yields of ions, noise, and the amount of ozone. Prototypes (2) and (3) were produced by extending the surface electrode 5 to have a triangular configuration (see FIG. 5). In the prototype (2), the width g was 0.45 mm and the height h was 0.45 mm, while, in the prototype (3), the width g was 0.35 mm and the height h was 0.3 mm. A prototype (7) had a conventional simple grid-like configuration, and the grid pitch was 0.8 mm. The applied voltage to the voltage applying circuit V was 70 to 90V, the potential difference between the peaks of the AC voltage was about 5.0 to 6.3 kV, and the frequency was about 40 kHz. The yield of positive ions, the yield of negative ions, the amount of ozone, and the noise value were measured under the above mentioned conditions. The results are shown in Table 1a,1b.

Note that the measurement of the yields of ions was performed at a measuring point about 25 cm apart from the ion generating element 1, and the measurement of the noise value was carried out at a measuring point about 11.5 cm apart from the ion generating element 1 in a noiseless room. Moreover, the inner electrode 6 was made to have a uniform strip form with a size of about 6 mm  $\times$  24 mm, and the width of lines forming the grid of the surface electrode 5 was made 0.25 mm in this experiment. Note that the "pitch" means the distance between the center line of one side of a grid

20

25

30

square and the center line of another side of the grid square.

As is clear from Table 1b, it was confirmed that the prototypes (2) and (3) generated ions in a more stable manner compared to the prototype (7) not only when the input voltage was high, but when the input voltage was low. Thus, by forming the grid-like surface electrode 5 to have further extended pointed parts, it is possible to generate ions in a stable manner with a wide range of voltage. Moreover, although noise increases with an increase in the yields of ions, since the prototypes (2) and (3) can be used with a low voltage as is clear from Table 1b, it is possible to limit noise. Furthermore, it was possible to significantly reduce the generation of ozone harmful to human body.

Next, prototypes (1), (4) and (5) were manufactured by changing the grid pitch, the width g, the height h and the distance f between the vertices of triangles (see FIG. 5), and similar experiments were carried out (the potential difference between the peaks of the AC voltage was made about 4.8 to 6.3 kV). The results are shown in Table 2a,2b.

As is clear from Table 2a,2b, in the case where the printing of the grid pattern of the surface electrode 5 was performed by changing the pitch from 1.0 mm to 1.5 mm and changing the size of the pointed triangle, when the pitch was small and the distance f between the vertices was small, the amounts of positive ions and negative ions were reduced. On the other hand, the noise value was lowered. This is caused by the fact that one side of the grid square is short, the electric field strength plane is small, and creeping discharges interfere with each other, and therefore stable generation of positive ions and negative ions can not be performed.

On the contrary, when the pitch is large and the distance f between the vertices is large, a large amount of positive ions and negative ions are generated, and accordingly the noise value increases. Thus, the lengths of the pitch and the distance f between the vertices establish a proportional relationship with the yields of positive ions and negative ions and the noise value. The inventors of the present application found from the experiments and the experimental data that, when stable ion generation and a reduction in the noise value are taken into consideration, the distance f between the vertices should not be less than 0.25 mm but not be more than 0.5 mm, and preferably be 0.35 mm as in the prototype (3), while the pitch should not be less than 1.0 mm but not be more than 1.5 mm, and preferably be 1.2 mm as in the prototype (3).

Finally, experiments were performed about an ion generating element 1 comprising the surface electrode 5 having a quadrangle configuration (see FIG. 6), under the same conditions as in the above mentioned experiments. Note that, in a prototype (8), the pitch was 1.2 mm, the distance f between the vertices was 0.5 mm, the length j between the point A and the point D shown in FIG. 6 was 0.15 mm, and the length k between the point E and the point D was 0.3 mm. The results are shown in Table 3a,3b.

As is clear from Table 3b, the results were as good as those of the prototypes (2) and (3), and stable ion generation was recognized in a wide range of voltage. The noise value was slightly higher, and it was caused as the distance f between the vertices inside the grid square was larger and the electric field was stronger. Note that it is conjectured that the noise problem can be solved by decreasing the distance f between the vertices.

#### INDUSTRIAL APPLICABILITY

10

15

20

25

30

As described in detail above, according to the present invention, on a surface of the dielectric body, in addition to the grid-like surface electrode, the pointed surface electrode is further formed inside the grid squares. More specifically, a triangle having two arbitrary points on a side of the grid square and an arbitrary point inside the grid square as the vertices, or a quadrangle having a crossing of grid lines, an arbitrary point near a straight line connecting crossings of grid lines in the diagonal positions, and two

arbitrary points on sides of the grid square as the vertices is formed as an extended part. Accordingly, by further providing the surface electrode with the pointed parts, it is possible to generate positive ions and negative ions in a stable manner in a wide range of voltage application. Consequently, ion generation at a low voltage becomes possible, and further noise and the generation of ozone can be effectively reduced by decreasing the voltage. Since the present invention can generate ions in a stable manner without particularly depending on the strength of the applied voltage, the present invention can give advantageous effects that the ion generating element of the present invention can be incorporated in many apparatuses regardless of the types of apparatuses and conditions of use such as home use and business use.

. 5

10

BETWEEN VERTICES 0.35 0.35 GRID SHAPE WIDTH HEIGHT SIMPLE 0.45 0.3 MOUNT 0.45 0.35 **Q**Q NUMBER IN LENGTH (=10.5) (=10.8) (mm) (=10.4) | mm | TABLE GRID SQUARE NUMBER IN WIDTH 19 (=28.5) mm) 23 (=27.6) mm.) 35 (=28.0 ) mm ) <del>.</del> പ 0,8 PROTOTYPE (3) PROTOTYPE (7) PROTOTYPE (2)

OZONE 0.0030.002 0.002 0.002 0.002 0.00 0.00 NOISE (4BA) 39.5 33.4 39.9 36. 4 POSITIVE NEGATIVE IONS IONS (NUMBER) 210000 190000 150000 200000 180000 30000 200000 180000 200000 190000 200000 50000 160000 220000 00006 220000 TABLE HIGH VOLTAGE (KVp-p) 5.56 6, 28 4.96 6.2 5.6 6.3 5.6 Ŋ INPUT VOLTAGE (AC:V) 06 06 06 80 70 90 PROTOTYPE (7) PROTOTYPE (2) PROTOTYPE (3)

TABLE 2a

		GRID	GRID SQUARE	Z	MOUNT SE	SHAPE
	- - - -	NUMBER	NUMBER	WIDTH	HEIGHT	WIDTH HEIGHT BETWEEN
	5	WIDTH	LENGTH	<i>p</i> 0	ح	VERTICES f
PROTOTYPE (1)	1.5	19/=28.5	7/=10.5	0.45	0.35	0.5
		/ mm /	/ mm /			
PROTOTYPE (2)	7.5			0.45	0.45	0.35
PROTOTYPE	1.2	23	9	0,35	0.3	0.35
2		( )	( mm )			
PROTOTYPE	1.2	٠	•	0.35	0,35	0.25
(+)						
PROTOTYPE	1	28	10	0.25	0.25	0.25
(2)		$\left(=28.0\right)$	(=10.9)			

NOISE (ABA) 39.5 33,4 39.9 37.2 42.1 44 40 36. .<del>.</del> 32. 33. POSITIVE NEGATIVE IONS IONS (NUMBER) 190000 180000 30000 230000 220000 200000 220000 200000 180000 70000 30000 40000 30000 00006 150000 160000 90009 30000 230000 200000 230000 180000 80000 260000 200000 180000 200000 200000 2 b TABLE HIGH VOLTAGE (kVp-p) 6.28 5.56 5.68 4.96 6.28 5.68 6.16 4.84 6.32 5.6 6.2 5.6 ഹ INPUT VOLTAGE (AC:V) 70 06 80 06 06 80 70 06 80 80 PROTOTYPE (1) PROTOTYPE (2) PROTOTYPE (3) PROTOTYPE (4) р<u>котот</u>үре (5)

PROTOTYPE 1.2 23 9 0.15 0.3 0.5 (8) (=27.6) (=10.8)

TABLE 36

INPUT HIGH 10NS 10NS 10NS (AC:V) (kVp-p) (kVp-p) (kVp-p) (220000 210000 42.8 (8) 80 5.56 210000 190000 38.3

#### **CLAIMS**

1. An ion generating element comprising: a dielectric body; an inner electrode formed inside said dielectric body; and a surface electrode formed on a surface of said dielectric body,

wherein said surface electrode is formed in a grid pattern and has a pointed part in each grid square.

2. The ion generating element as set forth in claim 1,

wherein said acuminate part is made of a triangle whose vertices are two arbitrary points on a side of the grid square and an arbitrary point inside the grid square.

3. The ion generating element as set forth in claim 2,

wherein a plurality of the triangles are formed for each grid square, and a distance between the vertices of the triangles inside the grid square is not less than 0.25 mm but not more than 0.5 mm.

4. The ion generating element as set forth in claim 1,

wherein said acuminate part is made of a quadrangle whose vertices are a crossing of grid lines, an arbitrary point near a straight line connecting crossings of grid lines in diagonal positions, and two arbitrary points on sides of the grid square.

5. The ion generating element as set forth in any one of claims 1

through 4,

wherein a pitch of the grid is not less than 1.0 mm but not more than 1.5 mm.

6. The ion generating element as set forth in any one of claims 1 through 5,

wherein said dielectric body has a plate-like shape, and said inner electrode lies inside the extent of said surface electrode.

7. An ion generating element comprising a plate-like dielectric body; an inner electrode formed inside said dielectric body; and a surface electrode formed on a surface of said dielectric body,

wherein said inner electrode lies inside the extent of said surface electrode.

- 8. An ion generator comprising: an ion generating element as set forth in any one of claims 1 through 7; and a voltage applying circuit for applying a voltage to the surface electrode and the inner electrode of said ion generating element, for generating  $H^+(H_2O)_n$  (n is a natural number) and  $O_2^-(H_2O)_m$  (m is a natural number) in the air by application of a voltage by said voltage applying circuit.
  - 9. An air conditioning apparatus including:

an ion generator comprising an ion generating element as set forth in any one of claims 1 through 7 and a voltage applying circuit for applying a voltage to the surface electrode and the inner electrode of said ion generating element, for generating  $H^+(H_2O)_n$  and  $O_2^-(H_2O)_m$  in the air by application of a voltage by said voltage applying circuit; and

a blower for sending ions generated by said ion generator to the outside.

#### 10. A cleaner including:

an ion generator comprising an ion generating element as set forth in any one of claims 1 through 7 and a voltage applying circuit for applying a voltage to the surface electrode and the inner electrode of said ion generating element, for generating  $H^+(H_2O)_n$  and  $O_2^-(H_2O)_m$  in the air by application of a voltage by said voltage applying circuit; and

a blower for sending ions generated by said ion generator out of said cleaner.

#### 11. A refrigerator including:

an ion generator comprising an ion generating element as set forth in any one of claims 1 through 7 and a voltage applying circuit for applying a voltage to the surface electrode and the inner electrode of said ion generating element, for generating  $H^+(H_2O)_n$  and  $O_2^-(H_2O)_m$  in the air by application of a voltage by said voltage applying circuit; and

a blower for sending ions generated by said ion generator into said refrigerator.

FIG. 1





FIG. 2



3/11

FIG. 3






FIG. 4



5/11








FIG. 7








FIG. 10





FIG. 11



Inte d Application No PCT/JP 02/08106

A. CLASSIFICATION OF SUBJECT MATTER
IPC 7 A61L9/22 H01T ĤOĨŤ23/00 According to International Patent Classification (IPC) or to both national classification and IPC B. FIELDS SEARCHED Minimum documentation searched (classification system followed by classification symbols) A61L H01T F24F Documentation searched other than minimum documentation to the extent that such documents are included in the fields searched Electronic data base consulted ouring the international search (name of data base and, where practical, search terms used) PAJ, EPO-Internal, WPI Data C. DOCUMENTS CONSIDERED TO BE RELEVANT Relevant to claim No. Citation of document, with indication, where appropriate, of the relevant passages Category 7-11 P,X PATENT ABSTRACTS OF JAPAN vol. 2002, no. 07, 3 July 2002 (2002-07-03) -& JP 2002 065838 A (SHARP CORP), 5 March 2002 (2002-03-05) abstract DE 44 20 038 A (ZELLWEGER MAX) 7-11 X 5 January 1995 (1995-01-05) column 3, line 56 -column 4, line 49 column 6, line 44 -column 7, line 11; 1-6 figure 5 US 5 227 192 A (ASANO KAZUO ET AL) 7,8 13 July 1993 (1993-07-13) column 2, line 65 -column 6, line 53 1-6 A -/--Further documents are fisted in the continuation of box C. Patent family members are listed in annex. Special categories of cited documents: \*T\* tater document published after the International filing date or priority date and not in conflict with the application but cited to understand the principle or theory underlying the "A" document defining the general state of the art which is not considered to be of particular relevance "E" earlier document but published on or after the international "X" document of particular relevance; the claimed invention cannot be considered novel or cannot be considered to "L" document which may throw doubts on priority claim(s) or which is cited to establish the publication date of another citation or other special reason (as specified) trivolve an inventive step when the document is taken alone document of particular relevance; the claimed invention cannot be considered to involve an inventive step when the document is combined with one or more other such docu-ments, such combination being obvious to a person skilled "O" document referring to an oral disclosure, use, exhibition or ocument published prior to the international filing date but later than the priority date claimed "&" document member of the same patent lamily Date of the actual completion of the International search Date of mailing of the international search report 25/11/2002 15 November 2002 Name and mailing address of the ISA **Authorized officer** European Patent Office, P.B. 5818 Patentiaan 2 NL - 2280 HV Rijswijk Tel. (+31-70) 340-2040, Tx. 31 651 epo nl, Fax: (+31-70) 340-3018 Maremonti, M

Inte 1281 Application No PCT/JP 02/08106

		PC1/JP 02/08108
	ntion) DOCUMENTS CONSIDERED TO BE RELEVANT	Refevent to claim No.
Category *	Citation of document, with indication, where appropriate, of the relevant passages	
Х .	US 4 155 093 A (CARRISH JEFFREY J ET AL) 15 May 1979 (1979-05-15) column 2, line 33 -column 3, line 11; claims 1-29; figures 1,7	7,8
X	PATENT ABSTRACTS OF JAPAN vol. 1997, no. 05, 30 May 1997 (1997-05-30) -& JP 09 007735 A (BIYOU:KK), 10 January 1997 (1997-01-10) abstract	7,8
		·
	·	
		·

PCT/JP 02/08106

Box I Observations where certain claims were found unsearchable (Continuation of item 1 of first sheet)
This International Search Report has not been established in respect of certain claims under Article 17(2)(a) for the following reasons:
Claims Nos.:     because they relate to subject matter not required to be searched by this Authority, namely:
2. Ctaims Nos.: because they relate to parts of the international Application that do not comply with the prescribed requirements to such an extent that no meaningful international Search can be carried out, specifically:
Claims Nos.:     because they are dependent claims and are not drafted in accordance with the second and third sentences of Rule 6.4(a).
Box II Observations where unity of invention is lacking (Continuation of item 2 of first sheet)
This International Searching Authority found multiple inventions in this international application, as follows:
see additional sheet
As all required additional search fees were timely paid by the applicant, this International Search Report covers all searchable claims.
2. X all searchable claims could be searched without effort justifying an additional fee, this Authority did not invite payment of any additional fee.
3. As only some of the required additional search fees were timely paid by the applicant, this international Search Report covers only those claims for which fees were paid, specifically claims Nos.:
4. No required additional search fees were timely paid by the applicant. Consequently, this international Search Report is restricted to the invention first mentioned in the claims; it is covered by claims Nos.:
Remark on Protest  The additional search fees were accompanied by the applicant's protest.  No protest accompanied the payment of additional search fees.

#### FURTHER INFORMATION CONTINUED FROM PCT/ISA/ 210

This International Searching Authority found multiple (groups of) inventions in this international application, as follows:

1. Claims: 1-6, 8-11 (partial)

Ion generating element comprising a surface electrode formed in a grid pattern with a pointed part in each grid square. Ion generator, air conditioner, air cleaner and refrigerator containing the same.

2. Claims: 7, 8-11 (partial)

Ion generating element comprising a surface electrode and an inner electrode that lies inside the extent of the surface electrode. Ion generator, air conditioner, air cleaner and refrigerator containing the same.

Information on patent family members

PCT/JP 02/08106

Patent document cited in search report		Publication date		Patent family member(s)	Publication date
JP 2002065838	A	05-03-2002	AU	7206901 A	26-11-2001
0, 500500000	••		WO	0187364 A1	22-11-2001
DE 4420038	A	05-01-1995	СН	685231 A5	15-05-1995
DE 44E0030	••	••	DE	4420038 A1	05-01-1995
			JP	2793128 B2	03-09-1998
•			JP	7144016 A	06-06-1995
US 5227192	A	13-07-1993	US	5202705 A	13-04-1993
US 4155093	Α	15-05-1979	AU	522601 B2	17-06-1982
03 4133030	••	••	AU	3883678 A	14-02-1980
t			BR	7805182 A	24-04-1979
			CA	1108685 A1	08-09-1981
			DE	2862435 D1	20-09-1984
			EP	0000789 A2	21-02-1979
•			ES	472517 A1	16-03-1979
•		•	JP	1634794 C	20-01-1992
			JP	2004904 B	30-01-1990
			JP	54053537 A	26-04-1979
			MX	145196 A	13-01-1982
JP 09007735 8	Α		NONE		